

Hydrostatic Test Procedure -- HE-3xx Series Heat Exchangers

Document ID: MP-HE-HYDROTEST-03

Issued: 2022-11-01 | Last reviewed: 2024-11-01
Applicable equipment: HE-301, HE-302, HE-303
Authority Level: 4 (Site Maintenance Procedure)

1. Purpose

Defines the hydrostatic test procedure and required test pressure for HE-3xx series heat exchangers following maintenance, repair, or scheduled integrity testing.

2. Test Pressure Calculation

Hydrotest pressure is set at 110% of the maximum operating pressure per the equipment's current operating specification.

3. Current Basis

Reference operating pressure	18.5 bar (per SOP-HE-GEN-11, current version on file)
Calculated hydrotest pressure	20.35 bar

4. Note on Pending Revision

OEM bulletin MHT-PB-2026-11 revises the reference operating pressure to 16.2 bar, which would change the calculated hydrotest pressure to 17.82 bar. This procedure has not yet been updated and is flagged under blast-radius analysis pending Management of Change resolution.